BRUHATH BANGALORE MAHANAGARA PALIKE

YALAHANKA ZONE ELECTRICAL DIVISION

Name of the work : Providing illumination in Nanjappa Circle,Doddabhommasandra circle, ananthpura Gate,Nagenahalli Gate,Kenchenahalli Gate,Vishal Mart 4Th Phase Yalahanka Traaffic police limit Ward No 02 & 10.

Est Cost **1500000.00**

Sl. No	SR Page No	Description	Unit	Qty	Rate	Amount
1	13/4.1.2	Fabricating, supplying and erecting swaged **tubular pole** of height ...Mtr having three sections, and providing two coats of red oxide paint and finished with two coats of enamelled paint of approved quality and colour and M.S. base plate of suitable size welded at the bottom of the pole(as per IS) and 40mm dia GI / flexible PVC pipe of 1 mtr length fitted to the heavy gauge polycarbonate control box including 5way connector of size 167x125x82mm for 7.5M pole/200x160x98mm for remaining length of pole with front opening cover, with locking arrangements and suitable capacity MCB / DP switch, The pole shall be erected in cement concrete work (1:2:4) including excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be up to 0.6M above ground level as per IS 2713 - 7.Erection of heavy duty pole on Footpath / median 9Mt (5Mt Hb,165.1mm dia 4.85mm thick x2M Hm, 139.7mm dia 4.50mm thick x 2M Ht,114.3mm dia 3.65mm thick) as per IS 410 SP 32	Nos	20	13200.00	264000.00
2	79/14.4.1	Supplying and fixing telescopic M.S. bracket fabricated by using 0.5m length 4" dia telescopic M. S. pipe, with 2" dia 1.5m long M. S. bracket and are welded with suitable angle, using 6mm thick M. S. sheet, grip bolts & nuts, as required, suitable for 9 to 12 Mtrs. M. S. tubular pole, with necessary two coats of painting, with all other accessories.Single bracket 1.5 Mtr. Length		8	1200.00	9600.00
3	79/14/4/3	Supplying and fixing telescopic M.S. bracket fabricated by using 0.5m length 4" dia telescopic M. S. pipe, with 2" dia 1.5m long M. S. bracket and are welded with suitable angle, using 6mm thick M. S. sheet, grip bolts & nuts, as required, suitable for 9 to 12 Mtrs. M. S. tubular pole, with necessary two coats of painting, with all other accessories.Double bracket 2x1.5 Mtr. Length	Each	4	1962.00	7848.00

4	67/12.9/6	Supply of LED floodlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/clear glass material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm.				0.00
		Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/ IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in- house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source.LED Floodlight 200W	Nos	24	18000.00	432000.00
5	67/12.8.5	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mouting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75 Luminaire manufacturer should have in-house	Nos	16	9200.00	147200.00

	14.5	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	Each	40	175.00	7000.00
7	40/6.4.5	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 5) 3.5 core 25 sqmm	Mtr	150	180.00	27000.00
8	41/6.5	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. 7) 25 sqmm to 75 sqmm	Rmt	150	35.00	5250.00
9	41/ 6.6	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) 2) In soil (ordinary)	Mtrs	100	76.00	7600.00
10	30/ 5.41	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. 2) 50x50x6mm	Per Mtr	30	330.00	9900.00
11	26/5.14	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE, 1) 100Amps 25kA.	Each	3	4530.00	13590.00
12	24/ 5.41	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. 4) 100Amps	Per Mtr	4	349.00	1396.00
13	30/5.42	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete. 1) 14SWG	Mtr	105000	0.40	42000.00
14	10/3.9	Supplying and fixing hylum plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc., and fixing on existing wood or metal box using N.F. screws.	Sqcm	30000	0.24	7200.00
15	5/2.3.2	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.10. sqmm	Mtrs	30	115.00	3450.00
16	40/6.1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 12 mm dia	No	3	2999.70	8999.10

17	41/6.3	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required.25x3mm GI strip	Mtrs	10	75.00	750.00
18	41/6.9.1	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV.40mm	Mtrs	8	335.00	2680.00
19	42/6.10.3	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.25Sqmm	Nos	3	350.00	1050.00
20	5/2.3.2	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.10. sqmm	Mtrs	30	115.00	3450.00
21	7/2.7.1	Wiring for lighting/power circuit using one of PVC insulated 1100V grade, stranded Aluminium wire single core in open or concealed system of wiring. 4 sqmm	Mtrs	400	9.00	3600.00
22	Pwd Sr	Hiring of 35 tons capacity Crane for releasing and refixing of High Mast	Hrs	50	548.00	27400.00
23	Pwd Sr	Supply of 12 MM Gi Steel wire rope 0.547Kgs/Meter	Mtrs	62	33.90	2101.80
24	2019-20 PWD Sr	Providing RCC Foundation for 12 Mtrs Mini high mast Datarate As per The Drawing and Civil estimate enclosed	Nos	2	29402.00	58804.00
25	2018-19 PWD Sr Page L1 Item 73	Hiring of tipper	Hrs	25	203.00	5075.00
						1098943.90
26	Ar	Thiristor based single/ Three phase smart street light control and monitoring system Remotely control and and monitorable smart street light system by using web or mobile application .smart control system has hardware ruggedness over field issues like line cross, line short, lighting and any other irregularities in voltage. It has some features like 1.Remote lighting management.2.Precise lighting turnoff.3.Load ballancing.4.Load power regulation.5.Status tracking. It works on the basis of some of these features 1) Main Control Unit (Mother board) : Handles controlling , data handling and other communication process. 2) Communication unit: GSM/GPRS quad bandwith RS232 interface wireless communication unit 3) Gate Driver Unit: Firing angle controllable board for driving the thyristor 4) Switching Thyristor: SCR 110 AMPS dual thyristor modules for switching 5) Embedded Firmware: Firmware to control , handle , process the data and communicate it wirelessly.6) Metal Enclosure : IP66 weather prof metal enclosure.7) Transformers: Customized step down transformers for various purposes.8) Wiring and other device assembly components.	Nos	3	51500.00	154500.00
27	56/7.6.4	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 25 + 1 X 25 SQ.MM	Per Mtr	500	144.00	72000.00

28	12/38.04	Stringing of 1.1kV grade aerial bunched 3 core cable of XLPE insulation of size (3x95) (for Phase conductor) + (1x70) (insulated messenger neutral) + (1x25) for street	Mtrs	500	22.46	11230.00
29	1/2.07	LT 2 Pin X Arms - MS (Dwg No. BESCOM/GM/QS&S/32 Dtd 24.11.2018	Nos	18	87.00	1566.00
30	2/5.01	RCC Pole clamp - MS (Dwg No. BESCOM/GM/QS&S/30 Dtd 24.11.2018)	Nos	18	53.00	954.00
31	13/42.12	Supplaying of Piercing Connector Suitable for 16 Sqmm - 95 Sqmm AB Cable - Street Light Connections	Nos	36	165.00	5940.00
32	13/42.16	Supplaying of Dead End Clamp/Anchor Clamp Assembly 25 to 95 Sqmm Bare Messenger(Exclusive of pole clamp and eye hook)	Nos	4	135.00	540.00
33	12/38.12	Installation of Insulation piercing connector for main to street light Main : 16-95sqmm, Tap : 1.5-10sqmm(EP95)	Nos	36	59.00	2124.00
34	12/38.1	Fixing of Universal/ Dead end Hook	Nos	4	127.00	508.00
35	42.19	Supplay of Suspension Clamp Assembly 16 to 70 Sqmm Bare Messenger(Exclusive of pole clamp and eye hook) 284845 No	Nos	18	196.00	3528.00
36	38.06	Erection of Suspension Clamp - 25 to 95 sqmm bare messenger		18	127.00	2286.00
		Total Rs				**1354119.90**
		GST 12 % on Item No 1 to 25 Rs		1098943.90		131873.27
		Bescom and Misscelleneous charges				14006.83
	TOTAL					**1500000.00**

CERTIFICATE

1. The place was inspected and work is essential
2. The place comes under BBMP limits.
3. The estimated prepared based on the PWD Electrical 2019-20 Rates and Bescom 2018-19

Asst. Engineer (Elec)

Asst. Exe.Engineer (Elec)
Sub-Division No.
Bruhat Bangalore Mahanagara Palike

EXECUTIVE ENGINEER (ELEC)
YELAHANKA DIVISION
BRUHAT BANGALORE MAHANAGARA PALIKE

Administrative Sanction for Rs. 15000000.00 RUPEES FIFTEEN LAKH ONLY is accorded under head PD300 M AND R TO STREET LIGHTS REPLACEMENT OF BURNT PACKAGE Registered as EE( ) No. 04/2021-22 Subject to conditions stipulated in enclosed memo No. BBMP/EE/EE/42/AS/04/2021-22 DT 17.07.2024

Executive Engineer

TECHNICALLY SANCTIONED FOR Rs. 15000000.00 RUPEES FIFTEEN LAKH ONLY Under PD300 M AND R TO STREET LIGHTS REPLACEMENT OF Registered as EE( ) No. 01/2021-22 Subject to conditions contained in enclosed memo EE( ) No. BBMP/EE/EE/42/15/04 Dt. 17.07.2021 Estimate is Sanctioned BBMP/EE/EE/42/TS/01/2021-22 Date 20.07.2021 Rs. 1500000.00